

STATUS: WARNING

SOP-003: Congestion Load-Shed Procedure

Effective Date: 2026-01-01 Owner: RAN Engineering Review Date: 2026-07-01

1. Trigger

This SOP is triggered when a tower experiences sustained load greater than 85% for more than 5 consecutive minutes.

2. Automated vs Manual Decision Table

Condition	Decision Path	Trigger
Load >85%, neighbours healthy	Automated	System auto-shed
Load >85%, neighbours congested	Manual	NOC + RAN intervention

3. Load-Shed Target Selection Rules

- Select nearest idle cell with available capacity.
- Prefer targets within the same cluster.
- Prioritise voice traffic over data during congestion.
- Minimise latency impact by avoiding cross-region redirection.

4. Step-by-Step Procedure

Step	Action	Owner	Time Target	Verification
1	Detect >85% threshold	System	Immediate	Threshold breach logged
2	Trigger auto-shed to designated neighbours	System	<3 min	Load reduced
3	Reprioritise voice over data on impacted tower	RAN	<5 min	QoS policy updated
4	If still >85% after 10 min - open capacity ticket P2	NOC	<15 min	Ticket created

5. Neighbour Cell Mapping

Tower	Primary Failover	Secondary Failover
TWR-OJO-002	TWR-OJO-005	TWR-LAG-W-022
TWR-LEK-003	TWR-LEK-008	TWR-LEK-014
TWR-LAG-W-014	TWR-LAG-W-022	TWR-LAG-W-031
TWR-IKJ-019	TWR-IKJ-021	TWR-IKJ-007
TWR-VI-002	TWR-VI-005	TWR-IKO-011
TWR-APP-004	TWR-AGE-009	TWR-OJO-002

6. KPI Targets

STATUS: WARNING

- Load-shed success rate >90%
- Response time <3 minutes

7. Version History

Version	Date	Change Summary
V1	2026-01-01	Initial release